

Aprobat  
PRIMAR  
ing Muresan Ioan Florin



## ANTEMASURATOARE

Executare canal pt fibra optica la sediul primariei Baciu.

1, Desfacere pavaj	5 mp
2, Spargere beton si escavare	1 mc
3, Sapatura	4,5 mc
4, Montat conducta PN 6DN 63	15 ml
5, Executat strat de nisip	1 mc
6, Exeutat umplutura	3 mc
7. Imprestiat compactat piatra sparta	0,40 mc
8, Executat strat support	2,5 mp
9, Montat pavaj	5 mp

Lucrari de alimentare cu apa a gradinitei din Suceagu.

1, Executat camin de apa	1 buc
2. Sapatura	12 mc
3, Taiere si spargere asphalt	15 mp
4. Montat conducta PN 6 DN 32	40 ml
5, Executat strat de nisip	2,5 mc
6. Executat umplutura	7 mc
7. Imprestiat compactat piatra sparta	3 mc
8. Turnat asphalt	1 mc
9, Transport pamint	5 mc
10. Transport asphalt	1 mc

Intocmit

Ing.Kovacs Gyorgy