

Aprobat
PRIMAR
ing Muresan Ioan Florin



ANTEMASURATOARE

Lucrari de reparatii la drumul communal localitatea Popesti.

Lungimea totala a celor 5 tronsoane de drum 350 ml cu latime de 4,5 m, va fi sapata la o adancime de 0,5 m.

1, Taiere, spargere carosabil asfalt si beton	45,00 ml
2, Excavare, evacuare pamant moloz	787,50 mc
3, Transport pamint, moloz la 5 km	1417,50 to
4, Strat de balast 15 cm grosime si compactare	236,25 mc
5, Transport balast	425,25 to
6, Strat de piatra sparta 35 cm grosime si comp.	551,25 mc
7, Transport piatra sparta de la 40 km	992,25 to
8, Curatire si amorsare suprafata	1575,00 mp
9, Mixtura asfaltica bad 26 -grosime 8 cm	126,00 mc
10, Transport asfalt la 30 km	302,40 to
11, Profilare sant	700,00 ml

Intocmit

Ing. Kovacs Gyorgy

Aprobat
PRIMAR

ing Muresan Ioan Florin



ANTEMASURATOARE

Lucrari de reparatii la drumul communal localitatea Corusu.

Lungimea tronsonului de drum 100 ml cu latime de 4 m, va fi sapata la o adancime de 0,5 m.

1, Taiere, spargere carosabil asfalt si beton	8,00 ml
2, Excavare, evacuare pamant moloz	200,00 mc
3, Transport pamint, moloz la 5 km	360,00 to
4, Strat de balast 15 cm grosime si compactare	60,00 mc
5, Transport balast	108,00 to
6. Strat de piatra sparta 35 cm grosime si comp.	140,00 mc
7, Transport piatra sparta de la 40 km	252,00 to
8, Curatire si amorsare suprafata	400,00 mp
9, Mixtura asfaltica bad 26 -grosime 8 cm	32,00 mc
10, Transport asfalt la 30 km	76,80 to
11, Profilare sant	200,00 ml

Intocmit

Ing. Kovacs Gyorgy