

Aprobat  
PRIMAR  
ing Muresan Ioan Florin



## ANTEMASURATOARE

Lucrari de reprofilare si pietruire drum in Popesti.  
Lungimea tronsonului de drum 350 ml, latimea de 4,00 m .

1, Reprofilare drum	350 ml
2, Transport pamant din reprofilare drum	220 mc
3, Piatra concasata 0-63	280 to
4, Piatra concasata 0-32	70 to
5, Transport piatra 35 km	350 to
6. Imprastiat piatra mecanic	220 mc
7, Cilindrare cu cilindru de 18 to	1400 mp

Intocmit

Ing.Kovacs Gyorgy